

# National Council for Promotion of Urdu Language

(Ministry of Education, Govt of India)

FC-33/9, Institutional Area Jasola, New Delhi – 110025

## Tender for Repair, Renovation and Maintenance of Building- National Council for Promotion of Urdu Language at Institutional Area Jasola New Delhi-110025.

Tender No NCPUL/Renovation/01/2024-25

Tender ID: 2024-NCPUL-819250-1)

Dated 08.08.2024

### **CORRIGENDUM -2**

#### **Financial Bid (BoQ)**

Existing				May be read as		
S.No. of item	Item Description	Qty	Unit	Item Description	Qty	Unit
11.12	Finishing walls with acrylic smooth exterior paint of required shad.	20	sqm	Finishing walls with acrylic smooth exterior paint of required shade: <b>(a) two or more coats on new work.</b>	20	sqm
14.05	Providing and placing in position <b>750 mm thick</b> factory made machine batched & machine mixed Precast RCC rectangular covers of drain on footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways , neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick , 100 mm wide MS sheet duly painted over priming coat , reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc including cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	10	sqm	Providing and placing in position <b>75 mm thick</b> factory made machine batched & machine mixed Precast RCC rectangular covers of drain on footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways , neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick , 100 mm wide MS sheet duly painted over priming coat , reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc including cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	10	sqm

This issues with the approval of competent authority.

Sd/-